7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

Quantity.	Items of Work.	Per.	Rate.
1,079	Earthwork excavation and filling the same in the basement ..	C. Yd.	
9,209	Concrete below foundation	C. Ft.	
14,193½	Foundation with brick in chunam	do	
5,051½	Basement with brick in chunam	do	
16,849	Superstructure, Lower story, with brick in chunam	do	
3,730	Superstructure, Upper story, brick in chunam . ..	do	
6,079½	Archwork with brick in chunam	do	
926	Cornice work	R. Ft.	
720	Thin cornice work to parapet	do	
70	Moulding work of windows, &c., ...	do	
8	Mantapam stone posts (cut) to Balcony each 1'×1'×7' including cutting base and top, &c, complete ..	Each.	
8	Brackets stones to Balcony at 1'×1'×4' including do ..	do	
1,555	Burnt stone slabs to steps	S. Ft.	
45·54	Tie rods of roof 1 " Dr.	Cwt.	
39·30	Fish plates, flat bar iron 4 " × ½"	do	
623·42	Plastering Lower story	Sqr.	
65·17	Do Upper story	do	
688·59	Whitewashing	do	
88·88	Flooring with slabs	do	
12·301	Segmental arched roof ⅛' thick including one course of flat tiles and concrete over roof..	C. Ft.	
2	Sets of centrings to arched roof	L. S.	
23·02	Terracing	Sqr.	
4	Door,s batten, including frames, bolts, hinges, &c., complete (No. 4. 4'×7') (No. 4. 3'×7')	Each.	
10	Battened windows to Lower story 3'×5' including iron bars, &c., complete	do	
2,361½	Do do 3'×6' do without iron bars ..	do	
603½	Planked supper boards to semicircular archways of verandahs, including frames, &c., complete	Sq. Ft.	
110·00	Teakwood work wrought and put up complete	C. Ft.	
2	Wood-oiling to wood work	Sqr.	
1	Ornamental work above balcony to parapets and gables ..	Each.	
4	Ornamental work of parapets on the sides of Upper story ..	L. S.	
4	Finials above pedestals of Upper story	Each.	
2	Ornamental brackets over parapets of Lower story . ..	do	
8	Ornamental key stones to main passage..	do	
	Ornamental columns at front and rear of Upper story ..	do	

STANDISH LEE,
Sanitary Engineer.

Visitors to the Mysore Government Museum, Bangalore, during the month of December 1888, *were* 17,747 *in number, averaging, exclusive of Sundays* 683 *daily.*

Signatures made in—										Total of Signatures.		Unable to sign but tally kept.	Total of Visitors.	Unable to sign No. of—		Total of Visitors.
English.		Tamil.	Telugu.	Kanarese.	Hindustani.	Mahratta.	Guzarati.	Malayalam.	Marwadi.	Males.	Females.			Men and Boys.	Women and Girls.	
Europeans.	Natives.															
603	1,554	801	193	1,322	380	40	3	6	6	4,700	208	12,839	17,747	6,943	5,896	17,747

J. CAMERON.